VXI BEAM ABORT	X332 U10		0710 BEAM_ABOR	ARC INTERLOCK CHASSIS	
HVPS BEAM ABORT	X332 U11		HVPS CONTROLS	HVPS HOFFMAN BOX	
HVPS ON REQUEST	X332 U12		0710 HVPS_ON	ARC INTERLOCK CHASSIS	
STATION ONLINE REQUEST	X332 U13		0710 FILAMENT	ARC INTERLOCK CHASSIS	Fast interlock Chassis End Lab swapped
FILAMENT AND FOCUS REQUEST	X332 U14		0710 SOLENOID	ARC INTERLOCK CHASSIS	Fast interlock Chassis End Lab swapped
FILAMENT TIMEOUT BYPASS	X332 U15		0710 TIMEOUT	ARC INTERLOCK CHASSIS	
RESET	X332 U16		0710 FAULT_RES	ARC INTERLOCK CHASSIS	
HVPS TRIGGERS ENABLE	X332 U19		HVPS CONTROLS	HVPS HOFFMAN BOX	
HVPS CROWBAR	X332 U20		HVPS CONTROLS	HVPS HOFFMAN BOX	
A-B HEARTBEAT	X332 U21		0710 HEARTBEAT	ARC INTERLOCK CHASSIS	
A-B SUMMARY	X332 U22		0710 A-B_SUM	ARC INTERLOCK CHASSIS	
	LOCAL PANEL				

SHEET 1 OF 1

PEPII RF CONTROL FIBER OPTICS

STANFORD LINEAR ACCELERATOR CENTER

STANFORD UNIVERSITY STANFORD, CA

ENGINEER ALAN HILL

DRAFTER. ALAN HILL

CHECKED. ALAN HILL

APPROVAL ALAN HILL

PEP II

RF SYSTEM

CONTROL FIBER OPTIC CABLES

WD-340-330-29-R0 | C

HFRO